





LENDAVA  HRVAŠKA 



LENDAVA 14.90



LENDAVA  HRVAŠKA 



BETONI:

**BETONI:**

- beton hodnikov in robnih vencev C30/37, XC4, XD3, XF4, PV-II, Dmax 32 mm
- beton vozniščne plošče C35/45, XD1, XF2, PV-II, Dmax 32 mm
- beton stebrov in opornikov s krili C30/37, XD2, XF2, PV-II, Dmax 32 mm
- beton gred nad piloti C30/37, XC2, PV-II, Dmax 32 mm
- beton pilotov in prehodnih plošč C25/30, XC2, PV-I, Dmax 32 mm
- podložni in naklonski beton C12/15

Krovni sloj betona:

- beton hodnikov in robnih vencev  $a = 4,5$  cm zgoraj,  $a = 3,5$  cm spoda

- beton hodnikov in robnih vevcev a = 4,5 cm zgoraj, a = 3,5 cm spodaj
- beton voziščne plošče a = 4,5 cm
- beton stebrov in gred nad stebri a = 4,5 cm
- beton opornikov in kril a = 4,5 cm
- beton gred nad piloti a = 5,0 cm
- beton pilotov a = 9,0 cm
- beton prehodnih plošč a = 5,0 cm

ARMATURA:

- rebrasta armatura: B500(B), visoko duktilno jeklo

- konstrukcijsko jeklo S235 J2, zaščiteno proti koroziji z vročim cinkanjem min 80  $\mu\text{m}$

[illegible]